

# Steel Shell For Pour In Place Installation 7 Ft. x 10 Ft. Brown

**MODEL SS/710**

Loading Dock Equipment / Electric Hydraulic Dock Levelers

Product image unavailable

## PRODUCT OVERVIEW

The electric Hydraulic Dock Leveler steel shell is an ideal addition to the dock leveler. The steel shells are installed when the concrete is being poured, to provide steel panels on each vertical face of the pit, along with steel flanges along the top faces. Proper installation of a dock leveler requires the leveler to be welded along the upper rear edge of the pit, and the steel shells provide this edge. The steel shells include a front lower steel angle, that gets placed at the front bottom of the pit. This angle provides another essential location where the leveler needs to be welded to the pit.

## KEY FEATURES

- Strong construction for long life
- Simple pour in place installation
- Perfect for mechanical or hydraulic dock levelers
- Positioned in place with minimal personnel

## CORE PRODUCT DATA

ASSEMBLED WEIGHT  
**473 lbs**

ASSEMBLED SIZE  
**92" W x 113" L x 24" H**

SHIP WEIGHT  
**473 lbs**

PACKAGE 1 SIZE  
**92" W x 113" D x 24" H**

COLOR / FINISH  
**Brown**

FREIGHT TYPE  
**LTL Palletized**

**AVAILABILITY** Available

Products are sold through Vestil distributor partners. Contact a distributor for current pricing and ordering.

**QUICKSHIP:** --

## ADDITIONAL PRODUCT VIEWS



PRODUCT SPECIFICATIONS

|                          |                                   |
|--------------------------|-----------------------------------|
| Maximum Board Width (In) | 92                                |
| Attachment Method        | Concrete pour in place            |
| Package Contents         | (1) Steel Shell for Dock Levelers |

PRODUCT & SHIPPING REFERENCE

Shipping Point: Angola, IN 46703

Warranty: 90 Days

AVAILABLE PRODUCT RESOURCES



SCAN FOR CURRENT PRODUCT DATA